



MBR.ST-35

Pre-Engineered Modular MBR Sewage Treatment System

The Clear³ (Clear-Cubed) MBR.ST-35 is a pre-engineered stand-alone decentralized modular treatment plant capable of treating sewage and waste water from residential, recreational, institutional and commercial developments up to **9,200 gallons per day**. The rugged, self-contained system is housed in a single modular building enclosure, built to meet local **weather conditions from extreme heat to extreme cold**. The Clear³ MBR.ST-35 is built on Newterra's years of membrane bioreactor experience and utilizes world class proven ZeeWeed[®] membranes for exceptional permeate quality that meets the **most stringent regulatory requirements** for reuse applications or discharge to sensitive receptors.

Influent & Effluent Limits

Designed for a range of wastewater strengths and the ability to meet the most stringent discharge and reuse requirements.

Flow Parameter	Influent From...	Effluent Limits
Biological Oxygen Demand (BOD ⁵)	200 to 400 mg/L	5 mg/L
Total Suspended Solids (TSS)	150 to 350 mg/L	5 mg/L
Total Kjeldhal Nitrogen (TKN)	35 to 70 mg/L	–
Total Ammania Nitrogen (TAN)	25 to 50 mg/L	1 mg/L
Total Nitrogen (TN)	–	5 mg/L *
Total Phosphorous (TP)	5 to 10 mg/L	0.1 mg/L *
Fat, Oil, and Grease (FOG)	Less than 30 mg/L	–
Fecal Coliform	–	2.2 MPN/100 mL**
Water Temperature	10 to 25°C	–
Turbidity	–	0.5 mg/L

*With nutrient reduction option(s) selected
 **With disinfection option(s) selected

Efficient Modular Design

- 20' long x 8' wide x 9.5' high
- Fully functional building including, but not limited to insulation, heating, ventilation, lighting, operator work space, and eyewash station
- Optional exterior finishings (color, siding, and/or roofing)



Design Flow Parameters

With robust biology and a broad turn-down capability the Clear³ MBR.ST-35 is designed around the following flow conditions.

Flow Parameter	Up To...
Average Daily Flow (ADF)	9,200 gal/day
Maximum Monthly Flow (MMF)	11,000 gal/day
Maximum Daily Flow (MDF)	18,400 gal/day



Clear³ Design Advantages

- Pre-fabricated modular facilities
- Rapid deployment
- Compact footprint
- Scalable
- Operator-friendly
- High-quality effluent
- No odor
- More discharge options
- Sound attenuation
- Reuse-ready effluent

About Newterra

Newterra offers a broad portfolio of reliable, trouble-free technologies and outsourcing support for global municipal and industrial customers across diverse applications, including drinking water, industrial process water, wastewater, stormwater and remediation.

What's Your Unique Water Question?

For just about any water problem, Newterra has you covered. Our temporary ownership and rental solutions can save precious capital while solving a critical need. Newterra offers flexible terms and conditions to suit any customer.

Contact us today at +1 800.420.4056 or visit us online at newterra.com





Clear³ MBR.ST-35

Pre-Engineered Modular MBR Sewage Treatment System

Base Unit Features

- Pre-treatment
- Flow equalization
- Aerobic biological treatment
- Membrane filtration with industry leading ZeeWeed® 500S membranes
- Sludge storage and thickening
- Advanced telemetry for remote control, monitoring & diagnostics
- Equipment or treatment train redundancy
- Low power, sludge production, and chemical consumption
- Pre-engineered for fast delivery
- Quality controlled factory assembled and tested
- MET/MET certified

Adders & Options

- Customized process design, tankage and equipment sizing
- Biological nutrient reduction, MLE process for denitrification
- Biological nutrient reduction, 4-stage bardenpho process for denitrification
- Coagulant dosing for phosphorous reduction
- UV disinfection
- Critical spare parts package
- Turbidity monitoring
- Sludge dewatering
- Increased chemical storage
- Building exterior finish (selection of colors, siding, roofing)
- Annual newtN™ service agreement

Flexible Tankage

The Clear³ MBR.ST Series is designed for use with a variety of in-ground tank configurations. This flexibility allows the benefits of a pre-engineered product, while using the best available tank configuration based on project specific site conditions and availability of labour and materials.



Basin	Required Volume
Trash Trap	5,600 gal
Equalization	5,600 gal
Aerobic	6,100 gal
Sludge Holding (30 days)	5,400 gal

Fiberglass

- 10' diameter FRP tanks provided by Newterra
- All in-tank components are factory installed prior to delivery
- Minimal mechanical and electrical site-work
- May not be suitable for all flow/loading conditions

Pre-Cast Concrete

- Pre-cast concrete tanks provided by Newterra or supplied locally
- Some mechanical and electrical site work
- All in-tank components are shipped loose for installation at site

Poured Concrete

- Poured in place concrete tanks supplied locally
- Smallest footprint of the tankage options
- More civil engineering and on-site civil, mechanical, and electrical work required
- All in-tank components are shipped loose for installation at site

SiteLink Advanced Remote Monitoring & Control

- Advanced cloud-based data acquisition and control
- Bank-level security
- A real-time link to the treatment system familiar HMI screen
- Email/text out upon alarm and a daily system status report
- Operating data is collected and available for download from the customer portal or locally at the HMI
- The customer portal also includes other useful information at your fingertips including manuals, troubleshooting guides, parts lists, etc.